

Project:1 Wardcraft Drive, Spring Arbor Range

Building Type: Commercial

Date Services Performed By: Services Performed For:


April 1, 2014 Parjana Inc. Parjana Distribution, LLC.

618 E. 10 Mile Road 1274 Library Street, Suite 600 Hazel Park, MI 48030 Detroit, MI 48226

Statement of Problem:

The current plans for the detention basin are not large enough. The current plan was to drain into the ditch and that plan cannot go through.

Quotation:



Engineering Notes:

The EGRP® system is effective on 250,000 square feet of the site. The EGRP® system can drain up to 205,000 gallons per hour. On a 1.25" rainfall over this area of 250,000 square feet there would be about 195,000 gallons of water. The EGRP® system may account for up to 1.25" of rainfall over this area.

The proposed detention basins are designed to have a total capacity of 6,331 cubic feet or 47,360 gallons.