

PARJANA

1274 Library Street, Suite 600, Detroit, MI 48226
Phone: 855-Parjana (855.727.5262) Fax: 313.228.1417

Website: Parjana.com Email: info@parjanadistribution.com

Project: 54301 Woodcreek Blvd, Shelby Township, MI, 48315, USA

Building Type: Residential

Date Services Performed By: Services Performed For:

May 22, 2014 Parjana & Parjana Distribution, LLC. John Jackson

1274 Library Street, Suite 600 Detroit, MI 48226

Statement of Problem:

The house has a high water table. It is ten years old and sump pump runs approximately every 60 seconds year round. There is iron ocre in the water and the builder installed 4 cleanouts so the homeowner can keep clear. Currently the homeowner has to flush out the draintile approximately every 45 days or the draintile will clog and he will get seepage into the basement. Homeowner indicated he bought the taller basement from the builder but they dug it deeper rather than pouring it higher above the grade. The neighbors on each side have normal depth basements and do not experience the same problems. The walls are great. No standing water issues, only floods when system is clogged; the the water runs over the footer and into the floor. There is an invisible fence and a sprinkler system. Paved patio, underground wiring. Majority of water appears to be coming from North side of house.

Quotation:



Engineering Notes:

Site must use at least five 40' EGRPs due to the unusually low basement. EGRPs must also go at least 4' below the footer.

Terms of Contract

Furnish labor and materials for the total installation of 2277-2783 Linear Feet of PARJANA® EGRP®- as shown in the first attached drawing.

All labor and materials for the installation of PARJANA® EGRP® are included. Warranty of the complete system for 25 years.

Anticipated cost based upon information provided to Parjana Distribution in accordance with standard EGRP specifications, for the estimated sum of:

Estimated Cost: \$21,403.8 - \$26,160.2

All material is guaranteed to be as specified in the final documents. All work to be completed according to standard practices. This proposal and its associated warranty certificate contain all of the terms and conditions agreed to by the parties and no other representations, warranties or agreements, expressed or implied, shall vary the terms of this contract.

